

Clean or Replace?

Decontamination Framework for Firefighting Equipment and Hangars

ER20-5361

Matthew Magnuson
US Environmental Protection Agency

July 22, 2021



Disclaimer

The views expressed in this presentation are those of the authors and do not reflect the official policy or position of the Air Force Institute of Technology, the United States Air Force, the Department of Defense, or the United States government. The U.S. EPA through its Office of Research and Development managed the research in this presentation. It does not necessarily reflect the Agency's views. Any mention of trade names, products, or services does not imply an endorsement by the EPA or the U.S. Government. EPA does not endorse the purchase or sale of any commercial products or services.

Project Team

- US Environmental Protection Agency
(Office of Research and Development)
 - Matthew Magnuson
 - Terra Haxton
 - Jonathan Burkhardt
 - Marc Mills
- US Air Force Institute of Technology
 - Lt Col John Stubbs (USAF)
 - Maj Trevor Sleight (USAF)
 - Maj Daniel Schurman (USMC)
 - Capt Jacob Spaulding (USMC)

Technical Objectives

- **Purpose:** Provide data and information to refine existing guidance about how to flush per- and polyfluoroalkyl substances (PFAS) from firefighting systems, specifically hangar systems and Aircraft Rescue and Firefighting (ARFF) vehicles
- **DOD Relevance:** As many as 4,350 DOD aqueous film forming foam (AFFF) delivery systems in aircraft hangars and firefighting vehicles may require decontamination. Unless effective cleaning solutions are available, replacement will cost \$2.1 billion, according to CBO.
- **Technical Gap:** No framework is available for evaluating cost and environmental impact of decontamination compared to costs of replacing components and systems.

Technical Questions

- How to ensure decontamination?
 - Potential PFAS rebound?
 - Is sampling necessary and how to do it?
 - For different systems?
- How to adapt decontamination protocols for one AFFF delivery system to a different one?
 - Construction
 - Age and system condition
 - AFFF exposure history
- Most useful format for protocols?

Test/Task Design

Task 1. Establishing a technical expert group of DOD and civilian experts from Airport Council International – North America

Task 2. Investigating decontamination protocols that take into account PFAS interaction with wetted surfaces

Task 3. Developing sample and analysis to avoid system recontamination

Task 4. Including small pipe hydraulics in models

Performance Summary

Task 1. Establishing technical expert group

Civilian: Airport Council International – North America

- 95% of domestic airports
- technical committees



DOD: PFAS Task Force,
AFCEC, CNIC, NAVAIR,
NAVFAC, USACE



SECRETARY OF DEFENSE
1000 DEFENSE PENTAGON
WASHINGTON, DC 20301-1000

7/23/19

MEMORANDUM FOR SECRETARIES OF THE MILITARY DEPARTMENTS
UNDER SECRETARY OF DEFENSE FOR ACQUISITION AND
SUSTAINMENT
UNDER SECRETARY OF DEFENSE (COMPTROLLER)/CHIEF
FINANCIAL OFFICER OF THE DEPARTMENT OF DEFENSE
UNDER SECRETARY OF DEFENSE FOR PERSONNEL AND
READINESS
GENERAL COUNSEL OF THE DEPARTMENT OF DEFENSE
ASSISTANT SECRETARY OF DEFENSE FOR LEGISLATIVE
AFFAIRS
ASSISTANT TO THE SECRETARY OF DEFENSE FOR PUBLIC
AFFAIRS

SUBJECT: Per- and Polyfluoroalkyl Substances Task Force

Releases of Per- and Polyfluorinated Alkyl Substances (PFAS) into the environment is a

Performance Summary

Task 4. Including small pipe hydraulics in predictive models

- **US Air Force Institute of Technology has developed working hydraulic models for ARFF and hangar systems**
- Piping system testbed being constructed at USEPA Test and Evaluation facility based on these design
- Model calibration parameters will be developed for PFAS, based on experimental results from testbed

Basis for Analysis (ARFF)


- Oshkosh P-19R

- Water Tank – 1000 gallons
- Foam Tank – 130 gallons
- Demands/Discharge
 - 500 gpm at turret
 - 250 gpm at bumper
 - Undertruck – 4 at 13 gpm
 - Hose Relay – 95 gpm
- Pressure Regimes
 - 200 – 350 psi (250 psi nominal)
- System Run Lengths
 - 8 – 15 feet on truck
 - 100 hose reel
- System Components
 - 304 Stainless Steel
 - Brass
 - Poly UPF® Tank




Schurman, AFIT-ENV-MS-21M-267
Distribution Statement B, TO Proprietary


P-19R Foam Delivery System




EPANET – Initial Condition



EPANET Demo





Example of Modelling-Enabled Results: Volume of Rinsate by Pipe Length and Flow Rate



ARFF Cost Estimate


- Monte Carlo methodology applied to cost. 3000 random values generated from +/- 10% of rinsate disposal costs
- Cost to rinse (simple water rinse to non-detect)
~\$1/gallon * ~1000 gallon/ARFF * 3000 ARFFs = \$3,000,000
- Cost to replace (NDAA and CBO estimate)
 - \$200,000 replacement cost for 3000 ARFF units
 - \$600,000,000 total

Basis of Analysis (Hangar)



Spaulding, AFIT-ENV-MS-21-M-273
Distribution Statement A

EPANET Model



Theoretical Triple Rinse

- $C = (0.0001\%) (C_0)$, Six-log reduction is 28.6 $\mu\text{g/L}$
- Flow rate 680 gpm
- Single rinse = 510 gallons, Triple rinse = 1,530 gallons
- Assumes no PFAS interaction with pipe wall

Rinse

1

2

3

4

Time (mins)	Chemical Concentration ($\mu\text{g/L}$)													
	Node 62	Node 64	Node 66	Node 68	Node 70	Node 72	Node 74	Node 76	Node 78	Node 80	Node 82	Node 84	Node 86	Node 88
0:00:00	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07
0:00:10	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07
0:00:20	2.86E+07	1.69E+07	2.82E+07	2.83E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07
0:00:30	2.86E+07	5343994	2.34E+07	2.40E+07	2.83E+07	2.28E+07	2.23E+07	2.83E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07
0:00:40	2.86E+07	937018.7	1.08E+07	1.21E+07	2.23E+07	1.11E+07	1.06E+07	2.18E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07	2.86E+07
0:00:50	2.86E+07	93999.33	1813753	2097407	1.08E+07	3112963	2943598	1.03E+07	2.54E+07	2.49E+07	2.84E+07	2.86E+07	2.86E+07	2.86E+07
0:01:00	2.36E+07	5416.31	112804.3	132191.3	3007782	508622.6	476494.2	2843960	1.62E+07	1.51E+07	2.56E+07	2.86E+07	2.84E+07	2.86E+07
0:01:10	1.16E+07	175.06	2698.83	3177.39	490054.9	48875.27	45517.42	459088.4	6570455	5756373	1.62E+07	2.84E+07	2.54E+07	2.86E+07
0:01:20	2072448	2.02	28.04	24.14	47012.1	2742.20	2544.2	42781.87	1620602	1250716	5280150	2.64E+07	1.58E+07	2.84E+07
0:01:30	388970.5	0.03	0.14	0.16	2635.06	87.21	80.72	2444.81	246321.5	197957	746692.6	1.88E+07	4882884	2.56E+07
0:01:40	24772.99	0	0	0	85.73	1.3	1.38	77.32	22318.79	17031.93	45218.37	7709701	897154.4	1.03E+07
0:01:50	712.08	0	0	0	1.44	0.01	0.01	1.33	1223.94	941.68	1007.19	1320860	45352.8	5696148
0:02:00	10.34	0	0	0	0.01	0	0	0.01	38.17	29.03	10.67	93262.38	1395.64	1004408
0:02:10	0.08	0	0	0	0	0	0	0	0.65	0.49	0.05	2975.63	22.13	91768.59
0:02:20	0	0	0	0	0	0	0	0	0.01	0	0	48.06	0.18	4423.62
0:02:30	0	0	0	0	0	0	0	0	0	0	0	0.4	0	119.81
0:02:40	0	0	0	0	0	0	0	0	0	0	0	0	0	1.87
0:02:50	0	0	0	0	0	0	0	0	0	0	0	0	0	0.02
0:03:00	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Hangar Cost Estimate

- Cost to rinse (simple water rinse to non-detect)
~\$1/gallon * ~2000 gallon = \$2000 per system
- Cost to replace (estimate from engineering firm)
 - Approximately \$150,000-\$250,000, including exchanging \$50,000 AFFF concentrate
 - Separate fees for waste disposal
 - **DOES NOT INCLUDE** cost/feasibility of hangar downtime

Performance Summary

Task 4. Including small pipe hydraulics in predictive models

- US Air Force Institute of Technology has developed working hydraulic models for ARFF and hangar systems
- **Piping system testbed being constructed at USEPA Test and Evaluation facility based on these design**
- Model calibration parameters will be developed for PFAS, based on experimental results from testbed

Experimental Site Description




- RCRA-permitted TSDF, adjacent to Greater Cincinnati WRRF
- High-bay (33,000 sq. ft.) and 5 labs, including BSL-2 lab
- Analytical instrumentation and machine shop

Pilot-Scale Hangar Piping Testbed



Current leak detection system being converted to hangar AFFF delivery system

EPANET Model of Hangar



What Pipes/materials?

AFFF delivery system is composed of:

- ◆ Unified Facilities Guide Specifications
 - Stainless steel (AFFF concentrate)
 - Black steel pipe (foam/water solution)
- ◆ Carbon steel (some commercial specs)
- ◆ Polypropylene (tanks)
- ◆ Others



From AFFF concentrate
stainless steel system



Key Points

- Use of modelling enables flexibility when priorities change
 - System type and construction specifics
 - Changes in discharge limits, if any
 - Desired volume of rinsate
- Inherent uncertainties may limit experimental solutions
 - AFFF adherence to system components may vary with component and experimental approach, limiting replication.
 - System specific conditions, including age and construction, may influence decontamination potential and approach.
 - Some systems and components may not be designed to be drained or accessed.

Applying Decontamination Protocols in the Face of Uncertainty

- How to ensure decontamination?
 - Potential PFAS rebound?
 - Is sampling necessary and how to do it?
 - For different systems?
- How to apply decontamination protocols for one AFFF delivery system to a different one?
 - Construction
 - Age and system condition
 - AFFF exposure history
- Most useful format for protocols?

Next Steps

- Complete construction of testbed at EPA-Cincinnati
- Establish reset conditions between experiments for assuring results represent realistic PFAS contamination.
- Validate hydraulic models with tracers and non-tracers, e.g., PFAS.
- Elucidate sampling procedure to verify decontamination
- Demonstration on actual ARFFs and hangars
- Transparent, consistent, and quantitative multi-criteria analysis approach for making decisions in the face of inherent uncertainties

BACKUP MATERIAL

These charts are required, but will only be briefed if questions arise.



ER-20-5361: Clean or Replace?

Decontamination Framework for Firefighting Equipment and Hangars

Performers: US Environmental Protection Agency,
US Air Force Institute of Technology

Technology Focus

- Standardized decontamination framework based on a toolbox of options utilized across the DOD and civilian aviation firefighting community

Demonstration Site

- Field site not currently available. Current studies at US EPA Test and Evaluation facility in Cincinnati, OH.

Demonstration Objectives

- Application of framework, including hydraulic model implementation, at specific demonstration site

Project Progress and Results

- Development of initial hydraulic model representing ARFFs and hangar system, thereby enabling construction of suitable testbed

Implementation

Coordination with other projects to minimize acquisition of duplicate data for elucidating sampling procedure is underway. It is unclear how much of the necessary data will ultimately be available.

